

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

NAME OF THE WORK:-Improvements to roads and drains in venkatappa layout in ward no.07, Byatarayanapura Kodigehalli Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	356.76	KSRRB 2-1.1: Earthwork in surface excvaton in ordinary soil for levelling and lowerng the ground manually (other than foundation of buildings, culverts road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exeeding 50m and lift upto 1.5m, excavated stuff to a distance not exceeding 50m and lift upto 1.5m excavated syrface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. (Pg No.5.Item No 2.1)	cum	166.42	Rupees One Hundred Sixty Six and Forty Two Paise Only
2	499.20	KSRRB 500-3: Scarifying existing stone metal layer upto 75mm thick along with their bituminous surface, picking up scarified materials and stacking of old serviceable materials with lead of 100m, sequential spreading of the salvaged aggregates with fresh aggregates on prepared base and consolidating as per water bound macadam specifications including cost of all labour, HOM of machineries complete as per specifications, MORTH chapter 5, No. 161 / Item No. 21.3	cum	92.22	Rupees Ninety Two and Twenty Two Paise Only
3	374.40	Providing granite slabs of selected quality roughly dressed and fixed in cements mortar (1:6) including fixing curing etc., complete. Pg No.25, Item No.5.31.1 (7.5 cms thick)	Sqm	665.68	Rupees Six Hundred Sixty Five and Sixty Eight Paise Only
4	355.68	KSRRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification . (Pg.No.12, It.4.3)	cum	5159.02	Rupees Five Thousand One Hundred Fifty Nine and Two Paise Only
5	249.60	Cement concrete pavement, Construction of un-reinforced plain cement concrete pavement, thickness as per deisgn, over a prepraed sub base with OPC cement or any other type as per clause 1051.2.2 with 25mm and down size graded granite metal coarse aggregates and fine aggregates ,with superplastiser @ 3lts confirming to IS9103-1999 REAFFIRMED-2008. Mixed in a concrete mixer of not less than 0.6 cum capacity and approximate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing) and spreading the concrete with shovels, rakers compacted using needle, screed and plate vibrator and finished in a continous operation including, provision of contraction, expansion, construction operation including longitudinal joints, including groove cutting charges joint filler, sparation menebrane, sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specification.M20 (AT 300 Kg per cum coarse aggregats @ 0.69cum and fine aggregate @0.43cum) (Pg No.177, It	cum	5508.82	Rupees Five Thousand Five Hundred Eight and Eighty Two Paise Only
6	9.98	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.(Page No.17, Item No.17)	cum	64243.42	Rupees Sixty Four Thousand Two Hundred Forty Three and Forty Two Paise Only
7	148.80	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular slabs /side walls polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge.(Page No 16, Item NO.4.32)	Sqm	387.96	Rupees Three Hundred Eighty Seven and Ninety Six Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
8	18.14	KSRRB 4.2.2: Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastizers @ 3lts confirming to IS 9103-1999 RE affirmed - 2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, stair case lintels, retaining walls return walls, walls(anythickness) including attached plasters columns piers abutments pillars posts struts buttresses string or lacing courses parapets copings, bed blocks , plain windows cills fillets etc., including cost of all materials labour HOM of machinery curing complete as per specifications. Seocifications No. KBS 4.1,4.6 (Page NO. 13, Item NO. 4.11)	cum	6371.66	Rupees Six Thousand Three Hundred Seventy One and Sixty Six Paise Only
9	41.25	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specifications (Data Rate Approved)	Sqm	2100.00	Rupees Two Thousand One Hundred Only
10	356.76	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 (Page 118, item No. 17.1)	cum	106.00	Rupees One Hundred Six Only


Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

- Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
- Unit rates and prices shall be quoted by the Tender in Indian rupees.
- Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Approved"


Chief Engineer
Yelahanka Zone
Jhath Bangalore Mahanagara
Bangalore 92

